

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the work: Estimate for Improvements to Roads and Drains at 2nd Main R/S C. Ramaiah Layout in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	353.40	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 142 / Item No. 19.1 / PWD SR 2016-17	Cum	199.36	
2	55.80	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. No. 12 / Item No. 4.3 / PWD SR 2016-17	Cum	5159.02	
3	117.18	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. Page No. 18 / Item No. 4.48 / PWD SR 2016-17	Cum	6231.74	
4	7.03	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 Page No. 17 / Item No. 4.46.2 / PWD SR 2016-17	Tonne	59413.00	

No correction - Nil

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
5	892.80	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15 / Item No. 4.31 / PWD SR 2016-17	Sqm	310.58	
6	334.80	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick Page No. 25 / Item No. 5.31.1/ PWD SR 2016-17	Sqm	665.68	
7	1857.00	KSRB 5-9: Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 Page No. 24 / Item No. 5.22 / PWD SR 2016-17	m	37.10	
8	334.80	KSRB 5-8.2 : Providing two line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5-1.13 Page No. 24 / Item No. 5.18 / PWD SR 2016-17	Sqm	963.54	
9	13.39	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. No. 12/ Item No. 4.6 / PWD SR 2016-17	Cum	5767.46	

NO of corrections - Nil

M. Chandrasekhar
Executive Engineer 12/01
Byatarayanapura Division
BBMP, Bangalore - 92

"DTS Approved" *12/01*

[Signature]
Chief Engineer
Yelahanka Zone
Bhath Bangalore Mahanagara
Bangalore 92
12.01.17